

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging off formations.

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Stafford County. Sec. 31 Twp. 21 Rge. (E) 12 (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines NWc SW NW

Lease Owner D.R. Lauck et.al

Lease Name Fischer Well No. 1

Office Address Wichita Kansas

Character of Well (Completed as Oil, Gas or Dry Hole) dry hole

Date, well completed Dec. 20 193 48

Application for plugging filed Dec. 20 193 48

Application for plugging approved Dec. 20 193 48

Plugging Commenced Dec. 20 193 48

Plugging Completed Dec. 31 193 48

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 193

Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? yes

Name of Conservation Agent who supervised plugging of this well Stough

Producing formation none Depth to top Bottom Total Depth of Well 3671 Feet.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	water	3668	3671	10	252	none
				5	3638	2450

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Gravel 3630

Cement 3630 - 3590

Mud 3590 210

Bridge 210 200

cement 200 165

mud 165 24

cement 24 6 bottom of cellar

RECEIVED  
JAN 13 1948  
STATE CORPORATION  
COMMISSION  
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to D. R. Lauck  
Address Wichita Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

P. R. Bishop (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-  
described well as filed and that the same are true and correct. So help me God.

(Signature)

520 Fourth Nat'l Bank Bldg. Wichita, Kans  
(Address)

SUBSCRIBED AND SWORN TO before me this 12 day of January, 1949

My commission expires Sept. 14, 1951

17-6058 10-38-5M

Notary Public.

**PLUGGING**  
FILE SEC 31 T 21 R 12  
BOOK PAGE 77 LINE 16

D.R. LAUCK et.al

Fischer No.1

Sec. 31 Twp.21S R12W

NWc SW NW

Commenced Nov.22, 1948

Completed Dec.9, 1948

Casing:

10" 252' cemented 300 sacks  
 5" 3638 cemented 75 sacks

Sand 219  
 Red Rock 450  
 Shale 700  
 Anhydrite 725  
 Shale & shells 1095  
 salt 1180  
 salt & shale 1330  
 shale & shells 1550  
 Lime & shale 2290  
 shale & shells 2455  
 Lime & shale 2940  
 lime 3005  
 shale & lime 3065  
 lime 3545  
 lime & chert 3595  
 shale 3638  
 lime 3640  
 Standardized  
 Lime 3643  
 slight rainbow  
 lime 3445  
 show free oil  
 lime 3647  
 500 acid  
 no help  
 lime 3667  
 1000 acid  
 no help  
 Lime 3670  
 some water  
 lime 3671

Tops- Derrick Floor

Heebner 3168  
 Brown lime 3296  
 Lansing 3313  
 chert 3558  
 Simpson 3590  
 Arbuckle 3636  
 Total Depth 3671

HFW

RECEIVED  
 Conservation Div.  
 JAN 20 1949  
 STATE OF KANSAS  
 COMMISSIONER

**PLUGGING**  
 FILE SEC 31 T 21 S R 12 W  
 BOOK PAGE 77 LINE 16