


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Stafford County, Sec. 31 Twp. 21S Rge. (E) 12 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW NE NW
Lease Owner Anschutz Drilling Company, Inc.
Lease Name Fischer "A" Well No. 1
Office Address 1307 $\frac{1}{2}$ Main Street, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 9 19 51
Application for plugging filed February 12 19 51
Application for plugging approved February 13 19 51
Plugging commenced February 14 19 51
Plugging completed February 22 19 51
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. D. Stough
Producing formation Arbuckle Depth to top 3652' Bottom 36 Total Depth of Well 3666 $\frac{1}{2}$ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	Water	3660	3666 $\frac{1}{2}$	5 $\frac{1}{2}$	3653	2882
Kansas City	Water	3431	3443			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug back to 3456' with Baker cast iron bridging plug

Plugged back to 3420' with chat, dumped 5 sacks cement to 3380'. Mudded hole to 336', set 10' rock bridge at 336', dumped 15 sacks cement at 326', mudded hole to 30' and set 10' rock bridge at 30'. Dumped 10 sacks cement filling hole to surface.

RECEIVED
STATE CORPORATION COMMISSION
FEB 27 1951
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Anschutz Drilling Company, Inc.
Address 1307 $\frac{1}{2}$ Main Street
Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Edw. C. Myers, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Edw. C. Myers, Jr.
1307 $\frac{1}{2}$ Main Street Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 26th day of February, 19 51.

My commission expires July 21, 1954 Notary Public.

PLUGGING
FILE SEC. 31-21-12
BOOK PAGE 61 LINE 18

DRILLER'S LOG

ANSCHUTZ DRILLING COMPANY, INC.
 #1 Fischer "A"
 NW NE NW SECTION 31-21S-12W
 STAFFORD COUNTY, KANSAS

0	160	Surface dirt & sand
160	322	Shale & shells
322	340	Red Bed
340	580	Red Rock & shells
580	7700	Red Bed & shale
700	725	Anhydrite
725	970	Shale & shells
970	1320	Shale, shells & salt
1320	1450	Shale & shells
1450	1560	Broken Lime
1560	1660	Lime
1660	1740	Sandy Lime
1740	1840	Lime Broken
1840	1940	Lime & sand
1940	2030	Lime & Shale
2030	2095	Lime
2095	2205	Shale & lime
2205	2285	Shale & lime
2285	2365	Shale & lime
2365	2490	Shale & lime
2490	2630	Shale & lime
2630	2745	Shale & lime
2745	2790	Shale & lime
2790	2830	Lime & shale
2830	2900	Shale & lime
2900	29400	Lime
2940	3045	Lime
3045	3117	Lime
3117	3170	Lime
3170	3240	Lime
3240	3305	Lime
3305	3355	Lime
3355	3400	Lime
3400	3445	Lime
3445	3455	Lime
3455	3505	Lime
3505	3550	Lime
3550	3592	Sandy lime & shale
3592	3635	Shale & chert
3635	3660	Shale & lime
3660		ROTARY TOTAL DEPTH

COMMENCED: 1/15/51
 COMPLETED: 1/27/51

TOPS:

Heeb.	3168	Corr.
Tor.	3190	"
B. L.	3297	"
Lans	3315	"
Cong.	3563	"
Vio.	3576	"
Simp.	3603	"
Arb.	3654	"
RTD	3659	"

CASING RECORD

Set 8-5/8" surface csg.
 @ 336' with 225 sacks
 cement.
 Set 5-1/2" oil string of
 casing @ 3655' with 100
 sacks cement.

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 14 1951
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS) /
) SS
 COUNTY OF SEDGWICK)

I hereby affirm that the above and foregoing is a true and correct copy of the log of the #1 Fischer "A" located in the NW NE NW of Section 31-21S-12W, Stafford County, Kansas.

ANSCHUTZ DRILLING COMPANY, INC.

H. R. Jensen
 HR. JENSEN

Subscribed and sworn to before me this 7th day of February, 1951.

Patricia Keener
 Notary Public

My commission expires: January 21, 1954.

