

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Stafford County. Sec. 30 Twp. 21 Rge. 12 (E) W (W)

Location as "NE/CNWxSWx" or footage from lines SW SE SW

Lease Owner Anschutz Drilling Company

Lease Name Fischer Well No. 3

Office Address Union Nat'l Bk Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 11-21 19 51

Application for plugging filed 3-9 19 53

Application for plugging approved 3-12 19 53

Plugging commenced 3-23 19 53

Plugging completed 3-30 19 53

Reason for abandonment of well or producing formation Production exhausted

If a producing well is abandoned, date of last production 3-1 19 53

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Arbuckle Depth to top 3641 Bottom 3701 Total Depth of Well 3701 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	341	
				5-1/2	3701	2827

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set bottom plug at 3345' - 5 sacks of cement on top -
rock bridge at 270' - 20 sacks cement on top -
rock bridge at 35' - 10 sacks cement on top

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Morgan Well Pulling Service

Address Hutchinson, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Leon L. Mehler

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Leon L. Mehler*

709 Union Nat'l Bk Bldg., Wichita, Ks.

(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of April, 19 53

My commission expires May 2, 1956

24-2675-S 2-52-20M

PLUGGING
FILE SEC. 30 T. 21 R. 12
BOOK PAGE 84 LINE 2

APR 10 1953
4-10-53
CONS. DIVISION
Wichita, Kansas

Anschutz Drilling Co. Inc.,
710 Union National Bank Bldg.,
Wichita, Kansas

Fisher #3

Commenced R.D.: 11-5-51
Completed R.D.: 11-21-51
Total Depth: 3705' R.T.
Casing Record: 344' of 8 5/8"

SW-SE-SW
Sec. 30-21-12
Stafford County, Kansas
Twin to Fisher #1
Elevation: 1870' D.F.
Initial Prod: Arbuckle
Contractor: Buick Drilling Inc.

Strata	Depth
Sand, Gravel & Clay	0 - 253
Clay & Shale	253 - 295
Sand	295 - 310
Clay & Shale	310 - 344
Red-Bed	344 - 465
Red-bed & Shale	465 - 695
Anhydrite Lime	695 - 720
Shale & Shells	720 - 1645
Lime & Shale	1645 - 3070
Broken Lime	3070 - 3147
Lime	3147 - 3208
Lime & Shale	3208 - 3272
Shale	3272 - 3303
Lime	3303 - 3339
Lime & Shale	3339 - 3465
Lime	3465 - 3569
Chert & Shale	3569 - 3603
Shale & Lime	3603 - 3641
Lime	3641 - 3705 T.D.

1672
695
77

I hereby certify the above a true and correct drilling log as reflected by the daily Drilling reports of the Buick Drilling Inc.

BUICK DRILLING INC.

H. R. Buick Pres.

Signed and sworn to in my presence this 1st day of Dec, 1951 by H. R. Buick, President of the Buick Drilling Inc.

Frank Jones
Notary Public

My Commission Expires: June 8 " 1953

PLUGGING
FILE SEC. 30-21-R-124
BOOK PAGE 84 LINE 1

STAFFORD COUNTY, KANSAS
RECORDS & SURVEY DIVISION
WICHITA, KANSAS