


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Stafford County, Sec. 30 Twp. 21 Rge. 12 (E) W (W)
Location as "NE/CNW*SW*" or footage from lines SW SE SW
Lease Owner Anschutz Drilling Company
Lease Name Fischer Well No. 1
Office Address Union Nat'l Bk Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 12-15 1950
Application for plugging filed 5-25-1953
Application for plugging approved 5-26 1953
Plugging commenced 6-13 1953
Plugging completed 6-18 1953
Reason for abandonment of well or producing formation Production depleted



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production June 1, 1953
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. River
Producing formation Lansing-K. C. Depth to top 3301 Bottom 3500 Total Depth of Well 3638 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	327'	
				5-1/2"	3636'	2836'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back to 3415' with rock-dumped 5 sacks
cement-mud back to 270'-5' rock bridge-ran 20
sacks cement-mud back to 35'-5' rock bridge-
ran 10 sacks cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ace Pipe Pulling Co.
Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Leon L. Mehler (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leon L. Mehler
709 Union Nat'l Bk Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of August, 1953

My commission expires May 2, 1956

24-2675-S 2-52-20M

RECEIVED
STATE CORPORATION COMMISSION

AUG - 4 1953
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 30 T 21 R 120
BOOK PAGE 103 LINE 31

DRILLER'S LOG
ANSCHUTZ DRILLING COMPANY, INC.
#1 FISCHER
SW SE SW - Section 30-21S-12W
STAFFORD COUNTY, KANSAS

0	210	Sand
210	330	Red bed
330	500	Red bed & shells
500	680	Red bed & shale
680	710	Anhydrite
710	945	Shale & shells
945	1265	Shale & shells and salt
1265	1460	Shale & shells
1460	1510	Broken lime
1510	1610	Lime
1610	1700	Lime
1700	1780	Lime
1780	1880	Lime
1880	1995	Lime & shale
1995	2070	Lime & shale
2070	2170	Lime & shale
2170	2295	Broken lime & shale
2295	2330	Lime & shale
2330	2435	Shale & shells
2435	2565	Shale & lime
2565	2670	Shale & lime
2670	2775	Lime & shale
2775	2885	Lime & shale
2885	2970	Lime
2970	3065	Lime
3065	3130	Lime
3130	3190	Lime
3190	3284	Shale & lime shells
3284	3285	Brown lime
3285	3345	Lime
3345	3430	Lime
3430	3525	Lime
3525	3570	Lime & chert
3570	3599	Chert
3599	3625	Shale & sand
3625	3635	Shale & lime
3635	3639	Lime
3639		ROTARY TOTAL DEPTH

COMMENCED: 12/1/50
COMPLETED: 12/22/50

TOPS

Heeb. 3155 (-1282)
B.L. 3284 (-1411)
Lans. 3301 (-1428)
Vio. 3547 (-1674)
Arb. 3636 (-1763)
TD 3643
(Cable)

CASING RECORD

Set 8-5/8" surface casing @ 327' with 225 sacks cement and 2 CC.

Set 5-1/2" oil string of casing @ 3636' with 150 sacks cement.

Swbd. 20 BOPH/4 hrs.
1000' off bottom, no water.

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I hereby affirm that the above and foregoing is a true and correct copy of the log of the #1 Fischer located in the SW SE SW of Section 30-21S-12W, Stafford County, Kansas.

ANSCHUTZ DRILLING COMPANY, INC.

BY: *M. W. Smith*
M. W. Smith

Subscribed and sworn to before me this 27th day of December, 1950.

James Heeb
Notary Public

My commission expires January 21, 1954.

RECEIVED
STATE CORPORATION COMMISSION

AUG - 4 1953

CONSERVATION DIVISION
Wichita, Kansas

