

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 30 Twp. 21 Rge. 12 (E) (W) X

Location as "NE/CNW%SW%" or footage from lines SW NE NE

Lease Owner Mobil Oil Corporation

Lease Name Fischer Well No. B-4

Office Address P. O. Box 1070 Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19 _____

Application for plugging filed 1-5-70 19 _____

Application for plugging approved 1-6-70 19 _____

Plugging commenced 1-27-70 19 _____

Plugging completed 1-31-70 19 _____

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph Warren

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3640 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	SIZE	PUT IN	PULLED OUT
		8 5/8	294	None
		5 1/2	None	2931'.33

RECEIVED
FEB 10 1970
CONSERVATION COMMISSION
WICHITA, KANSAS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Loaded unit and moved into location.

Raised pole and drove stakes. Took off production head. Made up and ran bailer to check hole. Pushed plug to 3,000' and plugged bottom off with 30 gal sand and 5 sacks of cement. Dug cellar and unpacked head. Set in sills, jacks and spiders. Took slips out of head, had 21" tension at 2,500 psi and 25" tension at 3,000 psi.

Checked hole for bridge. Build shot and shot casing at 2915'. Worked casing loose. Build slide and rack. Laid down 40 joints of 5 1/2" casing.

Finished laying down 29 joints of casing. Loaded out trailer. Cleared hole for plugging. Pushed plug to 280' and bridged hole with 10' of rock and 5' of sand. Mixed 3 sacks of cement and dumped with dump bailer - let set overnight.

Bailed water down in surface pipe. Dumped 25 sacks of cement to 180' and mudded to 30'. Dumped 10 sacks of cement to base of cellar. Tallied pipe. Well completed at 11:00 AM.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling Company, Inc.

Address P. O. Box 221 Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.

James w. Rockhold (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W Rockhold

P. O. Box 221 Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 6 day of February, 19 70

G. W. Ash

Notary Public.

My commission expires

May 27 1973

