

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202.

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-22,766.0000

LEASE NAME Wayne Fischer

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4950 Ft. from S Section Line

1150 Ft. from E Section Line

SEC. 30 TWP. 21 RGE. 12 (E) or (W)

COUNTY Stafford

Date Well Completed 4-23-91

Plugging Commenced 4-23-91

Plugging Completed 4-23-91

LEASE OPERATOR L.D. Drilling, Inc.

ADDRESS RR 1 Box 183B Great Bend, KS 67530

PHONE# (316) 793-3051 OPERATORS LICENSE NO. 6039

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-34-91 (date)

by Gene Barlow (KCC District Agent's Name).

Is ACO-1 filed? to be filed by operator If not, Is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 3631

Show depth and thickness of all water, oil and gas formations.

RECEIVED
STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
						APR 26 1991
						CONSERVATION DIVISION Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Bottom Plug: @ 700' w/50 sacks cement thru drill pipe
Next Plug: @ 360' w/50 " " " " " 15 Sacks in Rat Hole
Top Plug: @ 40' w/10 " " " " " 10 Sacks in Mouse Hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address P.O. Box 823 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: L. D. Drilling, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

John Armbruster (Employee of Operator) or ~~Operator~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) John Armbruster

(Address) P.O. Box 823 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 25th day of April, 19 91

Paula Ann Laudick
Notary Public

My Commission Expires:



DRILLER'S WELL LOG

DATE COMMENCED: April 17, 1991
 DATE COMPLETED: April 23, 1991

L. D. Drilling, Inc.
 WAYNE FISHER #1
 160 W of NW NE NE
 Sec. 30, T21S, R12W
 Stafford County, Ks.

0 - 682' Surface Soil, Sand, Clay
 682 - 704' Anhydrite
 704 - 1697' Shale
 1697 - 2058' Lime & Shale
 2058 - 2428' Shale w/Lime Streaks
 2428 - 3357' Lime & Shale
 3357 - 3502' Lime
 3502 - 3606' Chert & Lime
 3606 - 3631' Dolomite
 3631' RTD

ELEVATION: 1871 R.B.

Surface Pipe: Set new
 8-5/8", 23# pipe @333'
 w/225 sacks 60/40 pozmix
 2% gal 3% cc.


A F F I D A V I T

STATE OF KANSAS
 COUNTY OF BARTON) ss

John Armbruster of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

John Armbruster

Subscribed and sworn to before me this 25th day of April 1991.



Paula Ann Laudick
 Notary Public

RECEIVED
 STATE CORPORATION COMMISSION

APR 26 1991

CONSERVATION DIVISION
 Wichita, Kansas