

STATE OF KANSAS
STATE CORPORATION COMMISSION
10 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-21345-00-00

LEASE NAME W. Fisher

WELL NUMBER 1

330 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 30 TWP. 21S RGE. 12W (E) or (W)

COUNTY Stafford

Date Well Completed _____

Plugging Commenced 10-1-03

Plugging Completed 10-3-03

OCT 10 2003
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR GLOBE OPERATING, INC.

ADDRESS P.O. Box 12 Great Bend, Kansas 67530

PHONE# (620) 793-2891 OPERATORS LICENSE NO. 6170

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

This plugging proposal was approved on _____ (date)

by Steve Pfeifer (KCC District Agent's Name).

Is SACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom T.O. 3700'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	270'	None
				5-1/2"	3699'	2137'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging material is used, state the character of same and depth placed, from _____ feet to _____ feet each sack. Plugged off bottom with sand to 3600' and 5 sacks cement. Cut casing loose @2137', pulled up to 700', pumped 10 sacks gel, 100% hulls and 50 sacks cement. Pulled up to 300', pumped 50 sacks cement with 100% hulls, pulled up to 40' and circulated 20 sacks cement to the surface. 60/40 pos. 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Globe Operating, Inc.

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 9th day of October, 2003

[Signature]
Notary Public

My Commission Expires:

NOTARY PUBLIC - State of Kansas
IRENE HERZBERG
My Appt. Exp. 6-30-05

Form Revised 05-