


STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Blitting Building
Wichita, Kansas

WELL PLUGGING RECORD



Stafford County. Sec. 30 Twp. 21S Rge. 12W (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SW SW
Lease Owner Anschutz Drilling Company, Inc.
Lease Name Fischer Well No. 2
Office Address 709 Union National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 2/26 1951
Application for plugging filed 12/26 1951
Application for plugging approved 2/26 1951
Plugging commenced 2/26 1951
Plugging completed 2/26 1951
Reason for abandonment of well or producing formation Dry
If a producing well is abandoned, date of last production ----- 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. D. Stough, Great Bend, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3665 Feet
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	312'	-----

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom plug set @ 300' with 15 sacks cement
Top plug set @ 30' with 10 sacks cement.



(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Anschutz Drilling Company, Inc.
Address 709 Union Nat'l. Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick ss.
M. W. Smith (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *M. W. Smith*
709 Union Nat'l. Bk. Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 5th day of March 1951
Patricia Meeker
Patricia Meeker Notary Public.

My commission expires Jan. 21, 1954.

PLUGGING
FILE SEC 30T 21 R 12
BOOK PAGE 64 LINE 30

DRILLER'S LOG
 ANSCHUTZ DRILLING COMPANY, INC.
 #2 FISCHER
 SE SW SW - SEC. 30-21S-12W
 STAFFORD COUNTY, KANSAS

0	35	Sand
35	397	sand
397	685	Shale & shells
685	715	Anhydrite
715	780	Red Bed & shale
780	1150	Shale & shells
1150	1200	Shale
1200	1450	Salt
1450	1560	Shale
1560	1570	Sandy lime & shale
1570	1680	Lime & shale
1680	1865	Shale
1865	1990	Lime & shale
1990	2090	Lime & shale
2090	2250	Shale
2250	2375	Shale & shells
2375	2495	Shale & shells
2495	2585	Shale
2585	2720	Shale & shells
2720	2840	Shale & shells
2840	3143	Lime
3143	3205	Lime
3205	3290	Shale & lime
3290	3350	Lime
3350	3415	Lime
3415	3445	Lime
3445	3472	Lime
3472	3483	Lime
3483	3510	Lime
3510	3563	Lime
3563	3575	Shale & lime
3575	3600	Lime & chert
3600	3645	Shale
3645	3665	Lime
3665		ROTARY TOTAL DEPTH

COMMENCED: 2/14/51
 COMPLETED: 2/26/51

TOPS:

Heeb.1	3166
B. L.	3296
Lans.	3311
Det.	
Zone	3563
Arb.	3656
RTD	3665 (-1787)

CASING RECORD:

Set 8-5/8" surface casing
 @ 312' w/225 sacks cement
 and 2.00.

D & A

1878
 685
 1193

3665
 1787
 1878

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

I hereby affirm that the above and foregoing is a true and correct copy of the log of the #2 Fischer, located in the SE SW SW of Section 30-21S-12W, Stafford County, Kansas.

ANSCHUTZ DRILLING COMPANY, INC.

BY: *H. R. Jensen*
 H. R. Jensen

Subscribed and sworn to before me this 2nd day of March, 1951.

Loretta Becker
 Notary Public

My commission expires Jan. 21, 1954.

STATE COMMISSION
 MAR - 6 1951
 CONSERVATION DIVISION
 WICHITA, KANSAS

PLUGGING
 FILE SEC 30 T 21 R 12W
 DECK PAGE 64 LINE 30