

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Stafford County. Sec. 26 Twp. 21 Rge. 13 (W)

Location as "NE/CNW/SW" or footage from lines SW SW SW

Lease Owner M. B. Armer

Lease Name Dottie Smith Well No. 2

Office Address 710 Petroleum Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry

Date well completed Nov. 19 50

Application for plugging filed Nov. 26 19 50

Application for plugging approved Nov. 29 19 50

Plugging commenced Nov. 29 19 50

Plugging completed Nov. 30 19 50

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation Arbuckle Depth to top 3670 Bottom 3769 Total Depth of Well 3769 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				10-3/4"	263	none
				5 1/2"	3763	2632.70

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Lane Wells plug at 3417 ft., filled with chat from 3417 to 3380 ft., dumped 5 sacks cement at 3380 ft., ripped off & pulled 5 1/2" casing, filled with mud to 260 ft., set rock bridge and 20 sax cement at 260 ft. - mud to 30 ft., set rock bridge and 5 sax cement at surface.

RECEIVED
STATE CORPORATION COMMISSION
DEC 14 1950
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to M. B. Armer
Address 710 Petroleum Bldg., Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
L. C. Sponenberg (employee of owner) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
710 Petroleum Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of December, 19 50

[Signature] Notary Public.

My commission expires Sept. 17, 1951.

PLUGGING
FILE SEC-2127.1-32
BOOK PAGE 46 LINE 27

LOG

OWNER: M. B. Arner
CONTRACTOR: Speer Drilling Company
DRILLING COMMENCED: 10/14/50
DRILLING COMPLETED: 10/20/50
ELEVATION: 1875 (from old log)

FARM: Dottie Smith - well #2
(old Cities Service Schilling #2)
LOCATION: SW 26-21-13,
Stafford County, Kansas
CASING RECORD: 10" @ 263 (from old log)

5 1/2" OD casing cemented
@ 3763' with 175 sacks

(figures below indicate bottoms)

Washed out old hole	3733
Colomite	3769
Rotary Total Depth	3769

(old Arbuckle Top 3670')

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

SPEER DRILLING COMPANY

BY G. W. Speer

RECEIVED
STATE COMMISSION

DEC 14 1950

REGISTRATION DIVISION

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a notary public, for and for said County and State this 26th day of October, 1950.

Harold Walton
Notary Public

My commission expires: Sept. 17, 1951

PLUGGING
FILE SEC-21-21-R(2)
BOOK PAGE 46 LINE 27