

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGEN'T REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, Ks. 67202

API Number 15 -185-12908.0000 (of this well)

Operator's Full Name Petroleum, Inc.

Complete Address Box 1447, Great Bend, Ks. 67430

Lease Name Fischer "B" Well No. 1

Location SE NW NE Sec. 30 Twp. 21s Rge. 12 (E) (W) X

County Stafford Total Depth 3658

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereafter indicated

Plugging Contractor Rockhold Engineering, Inc.

Address Box 698, Great Bend, Ks. 67530 License No. 670

Operation Completed: Hour 12:15 PM Day 24 Month 5 Year 1980

The Above well was plugged as follows:

243' 8 5/8" casing w/200 sax cement. 4 1/2" casing set at 3656' w/150 sax
cement. Pref., at 3310'-Packer stuck at 3289'-Tubing off at 2680'-Sand
back to 2660'-Top sand w/ 4 sax mixed cement w/ dump bailer. Pull 1800'
casing-Sun mixed & pumped 8 sax hulls-25 sax gel-100 sax 50/50 posmix
w/4% gel & 3% ccin 8 5/8" casing back to 0'-Shut in w/ 500# pressure.

I hereby certify that the above well was plugged as herein stated.

RECEIVED
Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 5-30-80

INV. NO. 2247-w

MAY 27 1980

CONSERVATION DIVISION
Wichita, Kansas