

15-185.12670.0000

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 9 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Mobil Oil Corp.

Complete Address Box 1070 Great Bend, Ks 67530

Lease Name Fischer Well No. B -2

Location SE/NE/NE Sec. 30 Twp. 21 Rge. 12 (E) (W) X

County Stafford Total Depth 3614

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Forbes Casing Pulling Co.

Address Box 221 Great Bend, Ks License No. 49

Operation Completed: Hour 11:Am Day 7 Month 2 Year 1970

The above well was plugged as follows:

285 ft of 10 3/4 surface pipe circulated with 285 sacks cement.

3602 ft of 7" long string. Open hole. Sand back to 3590 ft, 6

sacks cement with bailer. 1800 ft of 7" pulled. Set bridge with

6 sacks cement. at 280 ft, 10 ft rock bridge, 30 sacks cement. Mud

to 40 ft, 10 ft rock bridge. 15 sacks cement to top of surface.

I hereby certify that the above well was plugged as herein stated.

Signed: A. Russell Biderston
Well Plugging Supervisor

INVOICED

DATE 2/9/70

INV. NO. 1396-U