

15.185.13197.0000

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
FEB 2 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Mobil Oil Corp.

Complete Address Box 1070 Great Bend, Ks 67530

Lease Name Fischer Well No. B-4

Location SW/NE/NE Sec. 30 Twp. 21 Rge. 12 (E) (W)^X

County Stafford Total Depth 3640

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Forbes Casing Pulling Co.

Address Box 221 Great Bend, Ks License No. 49

Operation Completed: Hour 11:30 AM Day 31 Month 1 Year 1970

The above well was plugged as follows:

294 ft of 8 5/8 surface pipe cemented with 225 sacks cement. Did

circulate. 3639 ft of 5 1/2 long string cemented with 100 sacks cement.

Top perf 3412 ft., Sand to 3400 ft & 5 sacks cement with bailer.

2915 ft of 5 1/2 pulled. Mud to 250 ft, 10 ft rock bridge, 25 sacks

sement, mud to 40 ft, 10 ft rock bridge. 10 sacks cement to surface

I hereby certify that the above well was plugged as herein stated.

Signed: A. Russell Bikerstein
Well Plugging Supervisor

INVOICED

DATE 2/2/70
INV. NO. 1347-W