



DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
 Conservation Division
 800 Bitting Building
 Wichita, Kansas

FILE NO. _____

LOCATION NE 1/4 - SE 1/4 S 1/2 SE

SEC. 30 TWP. 21 RGE. 18

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Fincher

Operator M. B. Oymer, Co Address 306 Insurance Bldg. Wichita, Kans.

Field _____ County Stafford

Total Depth 2621 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe - 8 1/2" - 278 ft. - Circulated with cement.
5 1/2" casing set at 3606 ft. - Filled back from
bottom to 3600 ft with chat - 5 sacks of cement
run in at 3600 ft. - Shot off & pulled the 5 1/2" casing
filled with mud to 250 ft. - Set Rock Bridge & 15 sacks
of cement at 250 ft. - Mud to 30 ft. - Plug & 10 sacks
of cement at the surface.

C. R. Stough
 District Conservation Agent

Date 7-18-49

PLUGGING
 FILE SEC 30 TWP 21 RGE 18
 BOOK 106 PAGE 11

JUL 20 1949 7-20-49
 ST. CONSERVATION