

15.185.12907.0000

Form CP-3
Rev. 6-26-62

76
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 10 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Woodman & Iannitti Oil Company

Complete Address: P. O. Box 387, Hoisington, Kansas

Lease Name Drach Well No. # 1

Location NE NE SE Sec. 30 Twp. 21 Rge. 12 (E) W

County Stafford Total Depth 3605'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 6:00PM Day 7th Month May Year 1965

The Above well was plugged as follows:

290' of 8 5/8" surface pipe, cement circulated. 3595' of 4 1/2" long
string, no cement record. This is an open hole. Bottom of the hole
was sanded to 3475', and cemented with 3 sacks. 610' of 4 1/2" long
string was recovered from the hole. Fluid in the hole was bailed
down to 200', bridge plug set on fluid at 200', and 10' of rock bridge,
and cemented with 25 sacks. Hole was filled with mud to 40', and 10'
of rock bridge, and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 5/10/65

INV. NO. 1126-W