

*B*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 39-11  
LOCATION C 7 1/2 NE-NE  
SEC. 30 TWP. 21 RGE. 12W

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 3 Lease Fischer "B"  
Operator Republic Natural Gas Co. Address Box 126 Ellinwood Kan  
Field \_\_\_\_\_ County Stafford  
Total Depth 3637 Feet.

(Describe briefly the manner in which the well was plugged)

8 1/8" 304' Circulated With cement  
5 1/2" 3597' cemented with 100 st. P.B. 3350'  
Perf to 3336' filled with sand to 3325' run 5 st  
cement with dump piles Mud to 340' set  
R.B. run 20 st cement Mud to 35' set R.B.  
run 10 st cement cap.  
R-S Paper pulling Co. #1  
Ellinwood Kan

RECEIVED  
STATE CORPORATION COMMISSION  
6-19-54 JUN 16 1954  
District Conservation Agent  
Wichita, Kansas  
Conservation Division  
Date 6-54

PLUGGING  
FILE SEC 30 TWP 21 RGE 12W  
BOOK PAGE 39 LINE 11


LOG

Company: Republic Natural Gas Company  
 Lease and Well: Fischer B-3  
 Location: C N/2 NE/4 NE/4 Section 30-21S-12W  
 County and State: Stafford County, Kansas  
 Commenced: 1-2-46  
 Completed: 1-25-46

0 - 235	Sand
235 - 245	Shale
245 - 683	Red bed
683 - 700	Anhydrite
700 - 1170	Red bed and shale
1170 - 1375	Shale and salt
1375 - 1490	Shale and shells
1490 - 1630	Broken lime and shells
1630 - 2170	Lime
2170 - 2300	Lime and shale
2300 - 2605	Shale
2605 - 2800	Shale and shells
2800 - 2850	Lime
2850 - 2960	Lime broken
2960 - 3073	Lime
3073 - 3293	Broken lime
3293 - 3535	Lime
3535 - 3550	Shale
3550 - 3599	Shale and lime
3599 - 3606	Lime
3606 - 3637	Arbuckle
3637	T.D.

Casing: 304' of 8-5/8" surface casing  
 cemented with 185 sacks of  
 cement.

3597' 6" of 5 1/2" production  
 casing cemented with 100 sacks  
 of cement.



RECEIVED  
 STAT. CO.  
 1946