

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 185 - 12669.0001 (of this well)

Operator's Full Name Mobil Oil Corporation.

Complete Address Box 5444 Denver, Colo. 80217

Lease Name Fischer "B" Well No. 1

Location C SE SE NE Sec. 30 Twp. 21 Rge. 12 (E) (W) X

County Stafford Total Depth 4030

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176 Chase, Ks. 67524 License No. 683

Operation Completed: Hour 12:30 Pm. Day 9 Month 6 Year 1979


The above well was plugged as follows:

306' 10 3/4" casing w/150 sax cement. 7" casing set @ 3602' w/100 sax
cement. 5 1/2" stub liner set @ 3574' to 3800' cemented w/100 sax cement.
4 1/2" casing set @ 3600' w/? sax cement. 7" casing parted @ 312'-Pull
312' 7" casing. 4 1/2" casing parted @ 1250'-Set bridge plug @ 1650'.
Cemented 4 1/2" casing to top of 10 3/4" casing. Allied mixed & Pumped
100 sax 50/50 posmix cement w/4% gel & 4% cc to top of casing. Shut in
w/ zero pressure. Total recovery-312'-7" casing.

RECEIVED
STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

JUN 15 1979
CONSERVATION DIVISION
Wichita, Kansas

Signed: 
Well Plugging Supervisor

INVOICED
DATE 6-12-79
INV. NO. 9820-W