

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
 Conservation Division
 211 North Broadway
 Wichita, Kansas

FILE NO. 119-28LOCATION NW-NW-NESEC. 26 TWP. 31 RGE. 13W

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease FanchierOperator Carl Todd Dry. Co. Address 404 K.F.H Bldg Wichita K.Field _____ County StaffordTotal Depth 3737 Feet.Plugging Contractor West Supply Co. Inc.Plugging Contractor's License No. 14Address Chase, Kansas

(Describe briefly the manner in which the well was plugged)

Surface pipe 8 7/8" @ 318' C.W.C. 5 1/2" set 3683'
 up 120 sq cem. Plugged back to 3500' top
 perf 3454' Sanded hole to 3445' and
 dumped 5 sq cem. shot off and pulled
 5 1/2" casing. Filled with mud. to 300'
 set rock bridge and dumped 20 sq cem.
 mud to 35' r. bridge and 10 sq cem. to
 base of cellar.

Warren S. Harner
 District Conservation Agent

RECEIVED
 STATE CORPORATION COMMISSION
 Date May 21, 1955

MAY 24 1955

CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 BOOK SEC. 26 T. 21 R. 13W
 PAGE 119 LINE 28