


DISTRICT CONSERVATION AGENT'S REPORT



TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SW-SW-SW

SEC. 26 TWP. 21 RGE. 13-W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease Dottie Smith

Operator Perry Drilling Co, Inc Address #710 Petera Bldg Wichita-Kans.

Field _____ County Stafford

Total Depth 3768 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 263 ft - Circulated with cement
5/8 casing set at 3768 ft - Cemented with 17 1/2 sacks cement.
Low Wells Plug at 3417 ft - Filled hole with
shot semen 3417 ft to 3385 ft - Dumped 4 sacks of
cement at 3385 ft - Ripped off & pulled the 5/8 casing
down to 260 ft - Set Rock Bridge & 20 sacks of cement
at 260 ft - Mud to 30 ft - Rock Bridge &
5 sacks of cement at the surface

12-4-50

PLUGGING
FILE SEC 26 TWP 21 R 13W
BOOK PAGE 46 LINE 27

C. D. Stough
District Conservation Agent

Date 11-30-50