

15.185.01731.0000

Form CP-3
Rev. 6-26-62

44
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
AUG 29 1966
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Herman Geo. Kaiser, Oil Producer

Complete Address: 909 Palace Bldg., Tulsa, Oklahoma

Lease Name Batman "A" Well No. # 2

Location NE SE SE Sec. 26 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3664'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling Company

Address: Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 1:30PM Day 27th Month August Year 1966

The Above well was plugged as follows:

203' of 8 5/8" surface pipe, cemented with 175 sacks. 3661' of 5 1/2" long
string, cemented with 125 sacks. This is an open hole. Bottom of the hole
was sanded to 3650', and cemented with 5 sacks. 1815' of 5 1/2" long string
was recovered from the hole. Bridge plug was pushed in fluid to 200', rock
bridge from 200' to 190'. 1 sack of cement and 1 sack of Cal-Seal was mixed
in a barrel, and put on plug at 190', through the dump bailer, and let set
for 4 hours. Hole was bailed dry, and filled with 2 1/2 yards of ready-mix
cement from 185' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 8/29/66
INV. NO. 3825-22

Signed: Archie Elving
Well Plugging Supervisor