

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued January 24, 1967.

RECEIVED
STATE CORPORATION COMMISSION

MAR 8 1967

CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Herman Geo. Kaiser

Complete Address: 909 Palace Bldg., Tulsa, Oklahoma

Lease Name Dottie Smith Well No. # 6

Location C E/2 SW Sec. 26 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3675'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling Company

Address: Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 4:30PM Day 6th Month March Year 1967

The Above well was plugged as follows:

285' of 8 5/8" surface pipe, cemented with 275 sacks. 3653' of 5 1/2" long string, cemented with 125 sacks. This is an open hole. Bottom of the hole was sanded to 3625', and cemented with 5 sacks, through the dump bailer. 2806' of 5 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid to 275', rock bridge from 275' to 255'. 3 sacks of cement and 1 sack of Cal-Seal was mixed in a barrel, and put on plug at 255', through the dump bailer, and let set for 4 hours. Hole was bailed dry, and filled with 3 yards of ready-mix cement from 240' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/8/67

INV. NO. 4882-w

Signed: Archie Elving
Well Plugging Supervisor