


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Westing Building  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Stafford County. Sec. 26 Twp. 21 Rge. (E) 13 (W)  
Location as "NE/CNW/SW" or footage from lines SW SW SE/4  
Lease Owner M. B. Armer  
Lease Name Batman "B" Well No. 1  
Office Address 710 Petroleum Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry  
Date well completed Sept. 5, 19 53  
Application for plugging filed Sept. 5, 19 53  
Application for plugging approved Sept. 5, 19 53  
Plugging commenced Sept. 5, 19 53  
Plugging completed Sept. 5, 19 53  
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3701 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	288	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy Rotary Mud to 280 ft.  
Set plug and cemented with 20 sacks cement  
through drill pipe. Mudded hole to 40 ft.  
set plug and 10 sacks cement at the surface.

RECEIVED  
STATE CORPORATION COMMISSION  
9-12-53  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor M. B. Armer  
Address 710 Petroleum Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
L. C. Sponenberg (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Sponenberg  
(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 11th day of September, 19 53

My commission expires FEBRUARY 13, 1956.

Rose Lurvey  
Notary Public.

PLUGGING  
FILE SEC 26 T 21 R 13W  
BOOK PAGE 127 LINE 27

KANSAS WELL LOG BUREAU--- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY M. B. Armer

SEC. 26 T. 21 R. 13W

FARM Batman B

NO. 1

LOC. SW SW SE

TOTAL DEPTH 3701'

COUNTY Stafford  
KANSAS


COMM. 8/25/53

COMP. 9/7/53

SHOT OR TREATED

CONTRACTOR M. B. Armer

ISSUED



CASING

20	10
15	8 288'
12	6
13	5

ELEVATION 1876 K.B.

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface Sand	85
Course Gravel	220
Shale & Gravel	260
Shale & Red Bed	288
Red Bed, Sand & Shale	705
Anhydrite	732
Shale	765
Shale & Shells	1355
Shale, Salt & Shells	1550
Shale & Lime	1865
Lime & Shale - Brkn	2000
Shale & Lime	2350
Shale & Shells	2600
Shale & Lime	3187
Shale & Lime - Broken	3234
Shale & Lime	3563
Shale, Lime & Chert	3689
Lime	3701

FORMATION TOPS (R.B. Meas.)

Heebner	3179	-1303
Brown Lime	3307	-1431
Lansing	3327	-1451
Viola	3571	-1695
Simpson	3645	-1769
Arbuckle	3690	-1814

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

M. B. Armer

*L. L. Spruill*  
NOTARY PUBLIC

STATE OF KANSAS  
COUNTY OF SEDGWICK

NOTARY PUBLIC  
DIVISION

Subscribed and sworn to before me, a notary public, in and for said County and State this 11th day of September, 1953.

*Rose Lusey*  
Notary Public

My commission expires February 13, 1956.

**PLUGGING**  
FILE SEC 26 T 21 R 13W  
BOOK PAGE 127 LINE 27