

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15.195.10670.0000

LEASE NAME Schulz D

WELL NUMBER #1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4950 Ft. from S Section Line

4950 Ft. from E Section Line

LEASE OPERATOR D. R. Lauck Oil Co., Inc.

SEC. 26 TWP. 21S RGE. 13 (E) or (W)

ADDRESS 221 S. Broadway, Suite 400, Wichita, Ks. 67202

COUNTY Stafford

PHONE# (316) 263-8267 OPERATORS LICENSE NO. 5427

Date Well Completed Nov. 2, 1956

Character of Well oil

Plugging Commenced Nov. 10, 1987

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed Nov. 10, 1987

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? Dist. #1, Dodge City, Ks.

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation KC & Arbuckle Depth to Top 3322 Bottom 3654 T.D. 3654

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
KC	oil & water	3322	3478	8-5/8"	231	none
Arbuckle	oil & water	3638	3654	5-1/2"	3638	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Allied Cementing Co. mixed 200 lbs. hulls followed w/200 sacks of ATL w/300 lbs. hulls mixed in. Max. pressure 600 lbs., shut in pressure 100 lbs. Unable to pump into surface pipe, Dakota has been squeezed.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor none License No. _____

Address _____

STATE OF _____ COUNTY OF _____, ss. DEC 9 4 1987

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Melvin L. Wilson

(Address) P.O. Box 488 Ellsworth Ks

SUBSCRIBED AND SWORN TO before me this 11th day of Dec, 19 87



My Commission Expires: 12-1-88

Notary Public

D. R. Lauck Oil Company, Inc.

Schulz "D" 1

NW NW NW Sec. 26-21S-13W
Stafford County, KansasCommenced: October 24, 1956
Completed: November 2, 1956Casing Record: 231' 8 5/8" cemented w/200 sacks
3638' 5 1/2" cemented w/175 sacks

Elevation: GR 1868; DF 1871; KB 1873

Drillers LogTops

		<u>Sample</u>	<u>Halliburton</u>
Surface clay	35	Anhydrite	714+1159
sand	150	Heebner	3160-1287 3162-1289
shale	290	Brown Lime	3290-1417 3292-1419
sand	305	Lansing KC	3307-1434 3308-1435
red bed	720	Base KC	3526-1652 3530-1657
shale & shells	1565	Viola	3562-1689
lime & shale	1970	Simpson shale	3590-1717 3594-1721
lime	2030	Arbuckle	3636-1763 3640-1767
sand	2040	Rotary TD	3639-1766 3643-1770
shale & lime	2450		
shale & shells	2650		
shale & lime	3100	DST #1 (W)	3327-3340 open 32 min.
lime	3160		strong blow 32 minutes; gas to
shale Heebner	3164		surface in 5 min. and flowed oil
lime & shales	3185		in 18 minutes. FP 315-670#,
shale	3290		BHP 1200# in 30 min.
lime	3585		
lime & chert	3590		
lime & shale	3636		
Arbuckle	3639		
rotary Total depth	3639		

RECORDED
STATE CORPORATION COMMISSION

OCT 22 1987

CONS. WALTER JOHNSON
Wichita, Kansas