

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-185-22,592-0000

LEASE NAME Pollie

WELL NUMBER 1-26

2970 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 26 TWP. 21 RGE. 13 (R) or (W)

COUNTY Stafford

Date Well Completed 7-11-89

Plugging Commenced 7-11-89

Plugging Completed 7-11-89

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Globe Exploration & Eldon Schierling

ADDRESS P.O. Box 12 Great Bend, KS 67530

PHONE#(316) 792-7607 OPERATORS LICENSE NO. 6170

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-10-89 (date)

by Dan Goodrow (KCC District Agent's Name).

Is ACO-1 filed? operator to be filed by operator If not, is well log attached? yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3760'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Bottom Plug: @ 740' w/50 sacks cement thru drill pipe

Next Plug: @ 290' w/40 " " " " "

Next Plug: @ 40' w/10 " " " " "  
15 sacks in rat hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc.

RECEIVED  
STATE CORPORATION COMMISSION  
License No. 5929

Address P.O. Box 823 Great Bend, KS 67530

JUL 14 1989

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Globe Exploration & Eldon Schierling

Wichita, Kansas

STATE OF Kansas COUNTY OF Barton, ss.

Leonard Williamson

(Employee of Operator) or ~~Operator~~ of


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Leonard Williamson

(Address) P.O. Box 823 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 13 day of July, 19 89

Dorothy M Hague  
Notary Public



DRILLER'S WELL LOG

DATE COMMENCED: July 6, 1989  
 DATE COMPLETED: July 11, 1989

Glove Expl. & Eldon  
 Schierling  
 "POLLIE #1-26"  
 SW SE NW  
 Sec. 26, T21S, R13W  
 Stafford County, Ks.

0 - 222' Surface Soil, Clay, Sand  
 222 - 710' Red Bed  
 710 - 734' Anhydrite  
 734 - 2031' Shale  
 2031 - 2836' Lime & Shale  
 2836 - 3183' Lime  
 3183 - 3207' Shale & Lime  
 3207 - 3216' Lime  
 3216 - 3310' Shale  
 3310 - 3325' Lime & Shale  
 3325 - 3555' Lime  
 3555 - 3672' Shale, Lime, Chert, Sand  
 3672 - 3754' Chert  
 3754 - 3760' Sand & Shale  
 3760' RTD

Elevation: 1871' K.B.

Surface Pipe: Set used  
 8-5/8", 32# @286'  
 w/150 sacks 60/40 pozmix  
 2% gal 3% cc.

## A F F I D A V I T


STATE OF KANSAS  
 COUNTY OF BARTON) ss

Leonard Williamson of lawful age does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

*Leonard Williamson*

Subscribed and sworn to before me this 13 day of July 1989

*Dorothy M. Hague*  
 Notary Public



RECEIVED  
 STATE CORPORATION COMMISSION

JUL 14 1989

CONSERVATION DIVISION  
 WICHITA, KANSAS