


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines Stafford County, Sec. 26 Twp. 21 Rge. 13 (E) (W) x C of E/2 SW
 Lease Owner Herman George Kaiser
 Lease Name Dottie Smith Well No. #6
 Office Address Box 666, Ellinwood, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) _____
 Date well completed _____ 19____
 Application for plugging filed _____ 19____
 Application for plugging approved _____ 19____
 Plugging commenced _____ 3-2-67 19____
 Plugging completed _____ 3-6-67 19____
 Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well Archie Elving
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3675' Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3653'	2815.74'
				8 5/8"	285'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Made bottom hole plug back with sand to 3640', mixed and ran 5 sacks cement thru dump bailer.
Mudded hole to 260', set 10' rock bridge. Mixed and ran 5 sacks cement thru dump bailer.
Bailed hole dry. Dumped 3 yards ready-mix to base of cellar.

FILED
STATE CORPORATION COMMISSION

MAR 8 1967

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
 Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer
Box 364, Great Bend, Kansas
 (Address)

SUBSCRIBED AND SWORN TO before me this 7 day of March, 19 67

My commission expires 24 October 1968
Sidney D. Miller
 Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

JAN 25 1967

CONSERVATION DIVISION
Wichita, Kansas

DRILLER'S LOG

COMPANY:	HERMAN GEORGE KAISER
CONTRACTOR:	LEBEN DRILLING, INC.
FARM:	DOTTIE SMITH #6
LOCATION:	C E/2 SW/4 SEC. 26-21S-13W
	STAFFORD COUNTY, KANSAS
COMMENCED:	10-16-60
COMPLETED:	10-28-60

0	40	Surface Clay & Sand
40	115	Sand
115	230	Shale & Sand
230	285	Shale & Shells
285	710	Redford
710	725	Anhydrite
725	735	Shale
735	740	Anhydrite
740	1600	Shale & Shells
1600	1825	Lime & Shale
1825	2110	Lime
2110	2530	Lime & Shale
2530	2885	Lime & Shale
2885	3245	Lime
3245	3355	Lime & Shale
3355	3365	Shale
3365	3396	Lime
3396	3453	Lime & Chert
3453	3500	Lime
3500	3605	Lime & Shale
3605	3626	Sand
3626	3650	Lime & Shale
3650	3670	Dolomite
	3670	<u>Rotary Total Depth</u>

Set 8 5/8" surface casing @ 285' with 275 sacks Sunset cement.
Set 5 1/2" casing @ 3653' with 125 sacks Posmix cement by Sun.

I, Frank Hamlin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Dottie Smith #6, located C E/2 SW/4 of Section 26, Township 21 South, Range 13 West, Stafford County, Kansas as reflected by the files of Leben Drilling, Inc.

Frank Hamlin
Frank Hamlin

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 10th day of November, 1960.

Bette J. Behymer
Bette J. Behymer, Notary Public

My Commission Expires:
July 27, 1964