


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Finney County, Sec. 24 Twp. 21 Rge. 34W E 24
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines
C NE SE

Lease Owner Maurice L. Brown Company
Lease Name Fleagle Well No. 1
Office Address 200 Sutton Place, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above Section Plat

Date Well completed 11/6/77 19
Application for plugging filed 11/6/77 19
Application for plugging approved 11/6/77 19
Plugging commenced 11/6/77 19
Plugging completed 11/6/77 19
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5020
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	T.D.	8-5/8	yes	no

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug at 360' with 50 sacks 50/50 Poz, 2% Gel
2nd plug at 40' with 10 sacks 50/50 Poz, 2% Gel
5 sacks in rathole
Job complete at 12:45 p.m. 11/6/77

RECEIVED
STATE CORPORATION COMMISSION

NOV 17 1977

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Slawson Drilling Company, Inc.
200 Douglas Building, Wichita, Kansas 67202


STATE OF Kansas COUNTY OF Sedgwick, ss.
James C. Remsberg (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James C. Remsberg
James C. Remsberg
200 Douglas Building, Wichita 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 15 day of November, 1977

Mary Lou Taylor
Mary Lou Taylor
Notary Public.

My commission expires January 17, 1981



DRILLERS LOG

OPERATOR: Maurice L. Brown Company
 200 Sutton Place
 Wichita, Kansas 67202

LEASE NAME: Fleagle No.1
 C NE 1/4 Sec. 24-21S-34W
 Finney County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.
 200 Douglas Building
 Wichita, Kansas 67202

COMMENCED: 10/22/77

COMPLETED: 11/6/77

RTD: 5020'

CASING: 8-5/8" set at 364' with 300 sacks cement

0' to 370' Surface Hole
 370' to 1760' Shale
 1760' to 2050' Shale & Shells
 2050' to 2068' Anhydrite
 2068' to 2398' Shale & Shells
 2398' to 2580' Shale & Lime
 2580' to 2580' Shale
 2580' to 2705' Shale & Lime
 2705' to 2870' Lime & Shale
 2870' to 3317' Shale & Lime
 3317' to 3536' Lime & Shale
 3536' to 3817' Lime
 3817' to 3918' Lime & Shale
 3918' to 4631' Lime
 4631' to 4700' Shale & Lime
 4700' to 4739' Lime
 4739' to 4813' Lime & Shale
 4813' to 5007' Lime
 5007' to 5020' Lime & Shale
 5020' RTD

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 17 1977
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS
 COUNTY OF SEDGWICK

I, James C. Remsberg, of the Slawson Drilling Company, Inc. hereby state that the above and foregoing is a true and accurate copy of the log of the Fleagle No.1 well for Maurice L. Brown.

James C. Remsberg
 James C. Remsberg

Subscribed and sworn to me this 15th day of November, 1977.

Mary Lou Taylor
 Mary Lou Taylor, Notary

My commission expires January 17, 1981.

