

9

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Finney County, Sec. 17 Twp. 21S Rge. 34 (~~EX~~ W) (W)
Location as "NE/CNW/SW" or footage from lines SW SW
Lease Owner Alpar Resources, Inc.
Lease Name Kester Well No. 1
Office Address Box 906, Perryton, Texas 79070
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 3, 1972
Application for plugging filed January 3, 1972
Application for plugging approved January 3, 1972
Plugging commenced January 6, 1972
Plugging completed January 6, 1972
Reason for abandonment of well or producing formation No productive Zone

NORTH



Locate well correctly on above
Section Flat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar Eyes
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5104 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	322	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Gunned up pits forming heavy mud. Filled hole with heavy mud. Spotted 30 sacks cement through drill pipe at 700 feet. Filled hole with heavy mud. Spotted 30 sacks cement through drill pipe at 320 feet. Filled hole with heavy mud, pushed plug to 40 feet and capped with 15 sacks cement to base of well cellar. Job complete at 2:00 PM, January 6, 1972.

RECEIVED
STATE CORPORATION COMMISSION
JAN 10 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Garvey Drilling Company
Address Box 1164, Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.
Ben E. Unruh (employee of owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ben E. Unruh
Box 1164, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of January 19 72

My commission expires July 8, 1974
James A. [Signature] Notary Public.

WELL LOG

COMPANY Alpar Resources

SEC. 17 T-21S R-34W

FARM Kester

NO. 1

LOC. SW SW


TOTAL DEPTH 5104'

COUNTY Finney, Kansas

COMM. 12-21-71

COMP. 1-6-72

CONTRACTOR Garvey Drilling Company



CASING

8 5/8" @ 322' w/250sx

ELEVATION

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

- 40' Clay & Sand
- 323' Shale
- 1465' Sand
- 1956' Red Bed & Shale
- 2190' Shale
- 2540' Shale & Lime
- 2945' Lime & Shale
- 4120' Lime
- 4310' Lime & Shale
- 4350' Lime
- 4500' Lime & Shale
- 4595' Lime
- 5104' Lime
- 5104' RTD

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 20 1972
 CONSERVATION DIVISION
 Wichita, Kansas

State of Kansas }
 County of Barton } SS

I, Charlene Marker of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Kester #1 well.

Charlene Marker

Subscribed and sworn to before me this 12th day of January 19 72

My Commission Expires: July 8, 1974

Gene A. Morris
 NOTARY PUBLIC