

STATE OF KANSAS
STATE CORPORATION COMMISSION


15-025-20206-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Clark County, Sec. 8 Twp. 30 Rge. 21 R/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
C SE/4

Lease Owner George R. Jones
Lease Name Hagenbuch. Well No. 1
Office Address 125 N. Market, Suite 1310, Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plat

Date Well completed April 8 1978
Application for plugging filed April 8 1978
Application for plugging approved April 8 1978
Plugging commenced April 8 1978
Plugging completed April 8 1978
Reason for abandonment of well or producing formation
Dry Hole

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas
Producing formation none Depth to top - Bottom - Total Depth of Well 5375
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				Ran 3 Jts. New 48# 13-3/8"	@ 118'	Cemented
				w/250 sxs. Common 3% CC;	Ran 15 Jts. 28#	
				8-5/8" @ 637'	Cemented w/250 sxs.	50/50
				Posmix 3% CC 150 sxs	Common 3% CC.	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug #1 @ 600' w/ 35 sx.;
Plug #2 @ 185' w/35 sx.;
Plug & bridge @ 40' w/10 sx.;
Rathole 5 sx.

RECEIVED
STATE CORPORATION COMMISSION

MAY 18 1978

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

George R. Jones ~~xxxxxxx or owner~~ or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George R. Jones
125 N. Market, Suite 1310, Wichita, Ks. 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of May, 1978

Mercedes Dobbins
Notary Public.

My commission expires

MERCEDES DOBBINS
STATE NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY APPT. EXP. FEB. 11, 1980

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

APR 21 1978

Hagenbuch #1
C-SE/4 Sec 8-30S-21W
Clark County Kansas

Commenced: 3-27-78

Completed: 4-8-78

OPERATOR: GEORGE R. JONES

From	Depth to	Formation	Remarks
0	20	Surface Clay	Ran 3 jts of New 48# 13 3/8"
20	95	Sand	csg set @ 118' Cemented w/
95	125	Clay-Sand	250 sks Common 3% CC
125	430	Clay-Redbed	PD @ 9:10 p.m. 3-27-78
430	2455	Shale	
2455	2624	Shale-Lime	Ran 15 jts of 28# 8 5/8" csg
2624	3335	Lime-Shale	set @ 637' Cemented w/
3335	3490	Shale-Lime	250 sks 50/50 Posmix 3% CC
3490	3655	Lime-Shale	150 sks Common 3% CC
3655	3765	Shale	PD @ 10:45 p.m. 3-28-78
3765	4448	Shale-Lime	
4448	4565	Lime-Shale	
4565	5375	Lime	
	5375		DRY & ABANDONED

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above Driller Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton II
JAMES S. SUTTON II

Subscribed and sworn to before me this 20th day of April, 1978.

Elizabeth J. Edwards
ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1979.

