

DRILLERS' WELL LOG

DATE COMMENCED: October 9, 1981
 DATE COMPLETED: October 17, 1981

L.D. Davis
 DRACH # 1
 SW NW SW
 Sec. 35-21S-13W
 Stafford Co., KS

0 - 264' Surface Soil, Shale, Red Bed
 264 - 734' Red Bed, Shale
 734 - 746' Anhydrite
 746 - 3206' Shale, Red Bed, Lime
 3206 - 3326' Shale & Lime
 3326 - 3345' Lime & Shale
 3345 - 3575' Lime
 3575 - 3704' Shale, Lime Chert
 3704 - 3760' Dolomite
 3760' RTD

ELEVATION: 1883 K. B.

FORMATION DATA

Anhydrite 734'
 Heobner 3206'
 Br. Lime 3326'
 Lansing 3345'
 Base KC 3575'
 Viola 3599'
 Arbuckle 3704'
 RTD 3760'

Surface Pipe: Set
 259' of 6 5/8", 20 #
 with 650 sacks Common,
 3% c.c., 2% gel.

AFFIDAVIT

STATE OF KANSAS
 COUNTY OF BARTON ss

RECEIVED
 STATE OF KANSAS
 CONSERVATION DIVISION

Wichita, Kansas

Darrel Anderson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Darrel Anderson

Subscribed and sworn to before me this 20 day of October 1981.

My Comm. Expires:

11-11-82

Dorothy M. Hoque

Notary Public