


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Stafford County, Sec. 35 Twp. 21 Rge. 13 (E) (W)  
Location as "NE/CNWK/SW" or footage from lines. NE SE SE  
Lease Owner Mobil Oil Company  
Lease Name R. C. Gates Well No. 5  
Office Address P. O. Box 1070 Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 5-7-65 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 5-18-65 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_  
Dry  
If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3658 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	280	None
				5 1/2	None	1828

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 21 1965

CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Moved in Casing pulling unit.  
Sanded hole back from 3665' to 3650'. Dumped 5 sacks of cement. Top of cement at P.B. 3610'.  
Digging out cellar, full to top of floor. Cutting cement with air hammer.  
Rigging up. Shot pipe at 2500' - 2000' - 1900' & 1800'. Pulling pipe.  
Finished pulling pipe.  
Set rock bridge at 175'. Dumped 5 sacks of cement.  
Spudding on bridge in surface pipe.  
Push plug in fluid to 200' and 10' rock bridge. Dumped 5 sacks of cement on plug at 190' through dump bailer. Let set over night.  
Bailed hole dry. Added 20 sacks of cement to plug. Mudded to 40'. Build 10' rock bridge and 10 sacks of cement to base cellar.  
Name of Plugging Contractor Forbes Casing Pulling, Inc.  
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) J. O. Forbes  
P. O. Box 221 Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 19 day of May 19 65

My commission expires May 27, 1969

Notary Public.

COMPANY: Magnolia Petroleum Company  
 CONTRACTOR: Mallard Drilling Company  
 FARM: R. C. Gates #5  
 LOCATION: SW SW NW Section 35-21S-13W  
 Stafford County, Kansas  
 COMMENCED: March 23, 1948  
 COMPLETED: April 4, 1948

6

0	to	255	Shale and sand
255	to	270	Red bed
270	to	280	Red bed
280	to	450	Red bed and shale
450	to	1050	Shale and shells
1050	to	1260	Shale and shells
1260	to	1380	Salt and shale
1380	to	1525	Shale and shells
1525	to	1975	Lime and shale
1975	to	2095	Lime
2095	to	2195	Lime and shale
2195	to	2350	Shale and lime
2350	to	2770	Shale and lime
2770	to	2985	Lime
2985	to	3105	Lime and shale
3105	to	3135	Lime
3135	to	3325	Shale and lime
3325	to	3608	Lime
3608	to	3653	Simpson shale
3653	to	3656	Shale
3656	to	3659	Lime and arbuckle
		3661	T. D. - KB

Set 280 feet of 8 5/8" surface pipe. Cemented with 300 sacks cement.

Set pipe at 3656 feet--5 1/2". Cemented with 150 sacks cement.

TOPS: Simpson--3608 Arbuckle--3656

Measurements taken from top of derrick floor.

RECEIVED  
 STATE CORPORATION COMMISSION

APR 23 1948

CONSERVATION DIVISION  
 Wichita, Kansas

C E R T I F I C A T E

I, C. C. Nelson, do hereby certify that the above and foregoing is a true and correct copy of the log of the Gates #5, Section 35-21S-13W, Stafford County, Kansas, as reflected by files of the Mallard Drilling Company.

*C. C. Nelson*

Subscribed and sworn to before me a Notary Public, within and for Sedgwick County, Kansas, this 8th day of April 1948.

*Maxwell Wright*

My commission expires 12/4/48