

6 060226

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 13-
SW, SEC. 21, T. 14 S, R. 16 W 16

1650 feet from WIS section line
2310 feet from W18 section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6050
Operator: Nelso Casing Pulling
Name & Address: Box 176, Chase, Mo. 67524

Lease Name Demonic Well # 2
County Ellis
Well Total Depth 3455' 112.29 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8" feet 989'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Nelso Casing Pulling License Number 6050

Address Box 176, Chase, Mo. 67524

Company to plug at: Hour: 8:00 AM Day: 15 Month: May Year: 19 84

Plugging proposal received from Mike Nelso

(company name) Nelso Casing Pulling (phone) 316-978-2457

were: Order 165 lb. Poposmia - 670 gal - 37 gal. U., 20 lb. Gel, 5 lb. hulls & 8 5/8" plug.

Plugging Proposal Received by Robert L. Helst
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 9:00 AM Day: 15 Month: May Year: 19 84

ACTUAL PLUGGING REPORT 8 5/8" - 989' cwc, 4 1/2" at 3453' w/150 lb.

Top perf at 3380'. Plugged bottom w/ 4 lb. cement, sand & 4 lb. cement to 3325'. Shot pipe 9 times & recovered 1950'. Pumped in 8 5/8" - 4 lb. hulls, 25 lb. cement, 15 lb. Gel, 70 lb. cement, 5 lb. Gel, 1 lb. hulls, released plug & followed w/ 70 lb. cement w/ 1000 pounds pressure.

Remarks: By Dan

INVOICED

I (did / did not) observe this plugging.

DATE 5-31-84

INV. NO. 1756

JUN 04 1984

Signed Robert L. Helst
(TECHNICIAN)

RECEIVED
CORPORATION COMMISSION
MAY 29 1984
CONSERVATION DIVISION
Wichita, Kansas