

15.051.30071.00.01

4-061210

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-051-03,796-0000

NW SE NE /4 SEC. 05, 14 S, 19 W
3630 feet from S section line
990 feet from E section line

Operator license# 30269

Lease: Werth Well # 1

Operator: Argent Energy, Inc.

County: Ellis

Address: 110 South Main - Suite #810
Wichita, Kansas 67202

Well total depth 3901 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 218 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Co Tools License#

Address:

Company to plug at: Hour: 9:30 A.M. Day: 1 Month: December Year: 1999

Plugging proposal received from: Dean Ives

Company: Argent Energy, Inc. Phone: 316-262-5111

Were: Order 350 sxs 60/40 pozmix - 10% gel and hulls - 15 sxs gel.
Low fluid level, well casing in condition.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour 10:30 A.M., Day: 1, Month: December, Year: 1999

Actual plugging report: 8 5/8" set to 218' w/175 sxs. 5 1/2" to 3891' w/125 sxs. Tied onto production casing and pumped 45 sxs cement with hulls followed by 15 sxs gel with hulls, followed by 155 sxs cement. Max. P.S.I. 2000#. S.I.P. 1500# Tied onto annulus with instant 500# S.I.P. indicating that annulus had been cemented.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD BAD X
Bottom plug(in place): YES , CALC X, NO
Plugged through TUBING , CASING X
Anhy.plug: YES X NO
Dakota plug: YES X
Elevation: 2283 GL

I did[] / did not[X] observe the plugging. KANSAS CORPORATION COMMISSION

INVOICED

DATE 12/21/99

INV. NO. 60973

RECEIVED [Signature]
AJA (agent)

DEC 09 1999

12-9-99

CONSERVATION DIVISION

Form CP-2/3

[Signature]