

15-185-21015.0000

1052285
TO: STATE CORPORATION COMMISSION

8-27

API NUMBER 15-185- 00-00
SW SE NE SEC. 4, T 21 S, R 13 W

CONSERVATION DIVISION - PLUGGING SECTION 2870 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 790 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME WILLCUT WELL # 3-1

TECHNICIAN'S PLUGGING REPORT COUNTY STAFFORD 115.12

OPERATOR LICENSE # 32081 WELL TOTAL DEPTH 3542 FEET

OPERATOR: SMOKEY VALLEY RESOURCES, INC PRODUCTION CSG: SIZE 4 1/2 " FEET 3539'

NAME AND 1325 HWY 56 SURFACE CASING: SIZE 8 5/8" FEET 283'

ADDRESS LYONS, KS 67554

ABANDONED OIL WELL, GAS WELL, INPUT WELL, SWD WELL, E-8784 D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524

COMPANY TO PLUG AT: HOUR: 1:30 PM DAY: 27 MONTH: 08 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM MANNY BOATRIGHT

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2943

WERE:

1ST PLUG BRIDGE PLUG AT 3360' WITH 2 SX CEMENT, 2ND PLUG AT 750' WITH 10 SX GEL & 50 SX CEMENT, 3RD PLUG AT 330' WITH 40 SX CEMENT, 4TH PLUG AT 40' WITH 10 SX CEMENT.

 PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 4:15 PM DAY: 27 MONTH: 08 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG BRIDGE PLUG AT 3360' WITH 2 SX CEMENT, 2ND PLUG AT 750' WITH 10 SX GEL & 50 SX CEMENT, 3RD PLUG AT 330' WITH 40 SX CEMENT, 4TH PLUG AT 40' WITH 10 SX CEMENT

RECEIVED
KANSAS STATE CORP COM
SEP 01 1998 11:51

REMARKS: 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1805' OF 4 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

INVOICED (I DID) OBSERVE THIS PLUGGING.

SIGNED Richard W. Lacey
(TECHNICIAN) FORM CP-2/3

DATE 9-2-98

INV. NO. 51259