

To: 1 120022  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5111

Operator: Rockhold Engineering  
Name & Address: Box 698  
Great Bend, KS 67530

9-28-87 15-185-00655-001  
API NUMBER 15- NA  
SE SE NW, SEC. 4, T 21 S, R 13 W/E  
2970 feet from S section line  
2970 feet from E section line  
Lease Name Schaffer Unit Well # 1-1  
County Stafford 117.16  
Well Total Depth 3605 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 217

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well X SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Engineering License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 11:30 a.m. Day: 28 Month: 9 Year: 1987

Plugging proposal received from Deacon Pulley

(company name) Rockhold Engineering (phone) 316-792-2506

were: 4 1/2" at 3603' Perfs at 3412-18'

1st plug sand back to 3350' and dump 4 sx cement on top of sand through bailer,

2nd plug pump in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2 p.m. Day: 28 Month: 9 Year: 1987

ACTUAL PLUGGING REPORT 1st plug sanded back to 3350' and dumped 4 sx cement on top of sand with a dump bailer,

2nd plug pumped in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 lbs. hulls,

50 sx cement, 10 sx gel, 50 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 200-300 psi and shut in 100 psi. OCT 5 1987

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2085' casing. (if additional description is necessary, use BACK of this form)

INVOICED

observe this plugging.

DATE 10-7-87

Signed [Signature] (TECHNICIAN)

CH. NO. 18417