

1080552

15.185.10541.0001

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- E-14,211  
NW NE SW, SEC. 4, T 21 S, R 13 W/E  
2310 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6050

Lease Name Koopman Well # 2  
County Stafford 117.23

Operator: Kelso Casing Pulling, Inc.  
Name & Address purchased from  
Kansas Gas Purchasing.  
P.O. Box 159  
Stafford, KS 67578

Well Total Depth 3607 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 10 3/4 feet 812

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well X Injection SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9:30 a.m. Day: 27 Month: 9 Year: 19 86

Plugging proposal received from Clay Duntz

(company name) Kelso (phone) 316-669-8614

were: 7" at 3606 Perfs 3530-43'

1st plug 1/2 sx hulls, 30 sx cement

2nd plug 6 hulls and 150 sx econolite

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10 a.m. Day: 27 Month: 9 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug 1/2 sx hulls, 30 sx cement 60/40 Pozmix 6% gel

stopped plug 2520' 400 psi shut in

RECEIVED  
STATE CORPORATION COMMISSION  
CONS. DIV. WICHITA, KS

2nd plug squeezed well with 3 sx hulls, mix 3 sx hulls with 150 sx ATL cement

Maximum pressure 600 psi and shut in 200 psi.

Fish at 2550' 2" tubing.

OCT 8 1986

Remarks: Recovered 1700' 7" casing. Cement by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-9-86

INV. NO. 15129

9-27

Signed J. A. [Signature] (TECHNICIAN)