

To: 1 120564
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

5-7 15.185.30390.0001 47R
E-14,211
API NUMBER 19-
NW SE SW, SEC. 4, T. 21 S. R. 13 W/E
990 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3911
Operator: Rama Operating Co.
Name & Address P.O. Box 159.
Stafford, KS 67578

Lease Name Koopman Well # 4
County Stafford 117.22
Well Total Depth 3607 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 245

Abandoned Oil Well _____ Gas Well _____ Input Well X SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 2:30 p.m. Day: 7 Month: 5 Year: 19 91

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 3600' w/110 sx cement, PBTB 3580', Perfs at 3556-65'

1st plug sand 4 1/2" casing back to 3500' and dump 4 sx cement on top of sand through bailer,

2nd plug pump in 8 5/8" surface casing with 350 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 150 lbs. hulls, and 125 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 6:30 p.m. Day: 7 Month: 5 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 3500' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 350 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 150 lbs. hulls and 125 sx cement.

Pumping pressure 0-400 psi and shut in 100 psi.

RECEIVED
STATE CORPORATION COMMISSION

MAY 13 1991

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1867' of 4 1/2" casing
(if additional description is necessary, use BACK of this form.)

INVOICED

(if additional description is necessary, use BACK of this form.) observe this plugging.

DATE 5-24-91

WV. NO. 31899

Signed Duane Rankin
(TECHNICIAN)