

1 120565

5-7 15.185.01684.0000 45
API NUMBER 15- Drill Completion Date 5/16/55 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NE SW, SEC. 4, T. 21 S, R. 13 W/EX

2310 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3911

Lease Name Koopman Well # 1

Operator: Rama Operating Company

County Stafford 117.13

Name & Address P.O. Box 159

Well Total Depth 3604 feet

Stafford, KS 67578

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 767

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 8:30 a.m. Day: 7 Month: 5 Year: 19 91

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 7" at 3603' w/100 sx cement, PBD 3567', Perfs at 3545-50'

1st plug sand 7" casing back to 3400' and dump 7 sx cement on top of sand through bailer,

2nd plug pump in 10 3/4" surface casing with 350 lbs. hulls, 6 sx gel, 75 sx cement,

14 sx gel, 150 lbs. hulls and 175 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1 p.m. Day: 7 Month: 5 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded 7" casing back to 3400' and dumped 7 sx cement

on top of sand through bailer,

2nd plug pumped into 10 3/4" surface casing with 350 lbs. hulls, 11 sx gel, 75 sx cement,

14 sx gel, 150 lbs. hulls and 175 sx cement.

Pumping pressure 0-600 psi and shut in 500 psi.

Welded plate and 5 1/2" collar on 10 3/4" surface casing.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1723' of 7" casing. CONSERVATION DIVISION Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED

(If applicable) observe this plugging.

DATE 5-24-91

Signed Duane Rankin (TECHNICIAN)

INV. NO. 31897

RECEIVED STATE CORPORATION COMMISSION

MAY 13 1991