

1 120566

S-7 15.195.10542.0000 46
API NUMBER 19- Drill Completion Date 6/27/57

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
300 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE NW SW, SEC. 4, T. 21 S, R. 13 WXX
1650 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3911
Operator: Rama Operating Company
Name & Address: P.O. Box 159
Stafford, KS 67578

Lease Name C.D. Koopman Well # 3
County Stafford 117.68
Well Total Depth 3621 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 792

Abandoned Oil Well Gas Well _____ Input Well _____ SHD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635
Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 1 p.m. Day: 7 Month: 5 Year: 19 91

Plugging proposal received from Gary Burke
(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711
were: 7" at 3621' w/100 sx cement, PBD 3563', Perfs at 3542-56'

1st plug sand back to 3450' and dump 7 sx cement on top of sand through bailer,
2nd plug pump in 10 3/4" surface casing with 350 lbs. hulls, 11 sx gel, 75 sx cement,
14 sx gel, 150 lbs. hulls and 175 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 7 Month: 5 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded 7" casing back to 3450' and dumped 7 sx cement
on top of sand through bailer,
2nd plug pumped into 10 3/4" surface casing with 350 lbs. hulls, 11 sx gel, 75 sx cement,
14 sx gel, 150 lbs. hulls and 175 sx cement.

Pumping pressure 0-700 psi and shut in 600 psi.

Welded plate and 5 1/2" collar on 10 3/4" surface casing.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1823' of 7" casing.
(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION

MAY 13 1991

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

observe this plugging.

DATE 5-24-91
INV. NO. 31898

Signed Duane Rankin
(TECHNICIAN)