

1052287

15-185-0167900-00
~~15-185-9017900-00~~

TO: STATE CORPORATION COMMISSION

8-27

API NUMBER DRILLED IN 1953
NE SE SE SEC. 4, T 21 S, R 13 W

CONSERVATION DIVISION - PLUGGING SECTION 990 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 330 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME WILLCUT LKC WELL # B-2

TECHNICIAN'S PLUGGING REPORT COUNTY STAFFORD 113.75

OPERATOR LICENSE # 32081 WELL TOTAL DEPTH 3500 FEET

OPERATOR: SMOKEY VALLEY RESOURCES, INC PRODUCTION CSG: SIZE 5 1/2 " FEET 3509'

NAME AND 1325 HWY 56 SURFACE CASING: SIZE 8 5/8" FEET 213'

ADDRESS LYONS, KS 67554

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL E-8784 D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 27 MONTH: 08 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM MIKE KELSO

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2943

WERE:

1ST PLUG PUMP DOWN 5 1/2" WITH 200# HULLS, 40 SX CEMENT, 15 SX GEL, & 80 SX CEMENT.

MAXIMUM PRESSURE 500 PSI, SHUT-IN PRESSURE 100PSI.

2ND PLUG PUMP DOWN 8 5/8 X 5 1/2 ANNULAS WITH 100 SX CEMENT. MAXIMUM PRESSURE 1000#.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 11:30 PM DAY: 27 MONTH: 08 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG PUMPED DOWN 5 1/2" WITH 200# HULLS, 40 SX CEMENT, 15 SX GEL, & 80 SX CEMENT.

MAXIMUM PRESSURE 500 PSI, SHUT-IN PRESSURE 100PSI.

2ND PLUG PUMPED DOWN 8 5/8 X 5 1/2 ANNULAS WITH 100 SX CEMENT. MAXIMUM PRESSURE 1000#.

REMARKS: 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (THE) OBSERVE THIS PLUGGING.

DATE 9-2-98

SIGNED Richard W. Lacey (TECHNICIAN) FORM CP-2/3

INV. NO. 51257

8-27 JAN 29 1999

RECEIVED
STATE CORPORATION COMMISSION
SEP 01 1998
51