

1 120021

9-28-87

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- NA 15.185.01693.0000

NE SE NW, SEC. 4, T 21 S, R 13 W/E  
3630 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5238

Lease Name Schaffer Unit Well # 1-2

Operator: Petroleum Inc.

County Stafford 116.32

Name & Address Box 1447

Well Total Depth 3579 feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 211

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Rockhold Engineering License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 8 a.m. Day: 28 Month: 9 Year: 19 87

Plugging proposal received from Deacon Pulley

(company name) Rockhold Engineering (phone) 316-792-2506

were: 5 1/2" at 3569' Perfs at 3410-16'

1st plug sand back to 3360' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release  
8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Paul Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 11 a.m. Day: 28 Month: 9 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 3360' and dumped 5 sx cement with a dump  
bailer on top of sand,  
2nd plug pumped in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 lbs. hulls,  
50 sx cement, 10 sx gel, 50 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 200-400 psi and shut in 150 psi.

10-5-87

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2080' of 5 1/2" casing.

RECEIVED  
STATE CORPORATION COMMISSION

INVOICED

(If additional description is necessary, use BACK of this form.)

I (dfd / 870787) observe this plugging.

DATE 10-7-87

Signed [Signature] (TECHNICIAN)

CONSERVATION DIVISION  
Wichita, Kansas

W.P. NO. 18414