

To: 1 120024
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

9-28-87
API NUMBER 15- NA 15.195.01680.0000

SW NW NE, SEC. 4, T 21 S, R 13 W/E
4290 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5111

Lease Name Schaffer Unit Well # 2-1

Operator: Rockhold Engineering
Name & Address: Box 698
Great Bend, KS 67530

County Stafford 116.48
Well Total Depth 3584 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 240

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 3:30 p.m. Day: 28 Month: 9 Year: 19 87

Plugging proposal received from Deacon Pulley

(company name) Rockhold Engineering (phone) 316-792-2506

were: 4 1/2" at 3582' Perfs at 3406-13'

1st plug sand back to 3350' and dump 4 sx cement on top of sand through bailer,
2nd plug pump in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 lbs. hulls,
50 sx cement, 10 sx gel, 50 lbs. hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 p.m. Day: 28 Month: 9 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 3350' and dumped 4 sx cement on top of sand through dump bailer,

2nd plug pumped in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 lbs. hulls, 50 sx cement, 10 sx gel, 50 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 200-400 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2096.68' of 4 1/2" casing.

RECEIVED
STATE CORPORATION COMMISSION
OCT 5 1987

(If additional description is necessary, use BACK of this form)

INVOICED

observe this plugging.

DATE 10-7-87

Signed [Signature] CONSERVATION DIVISION
Wichita, Kansas (TECHNICIAN)

INV. NO. 18416