

To: 1 120025  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

9-28-87 15.185-01678.0000  
API NUMBER 15- NA

TECHNICIAN'S PLUGGING REPORT

Operator License # 5238

Operator: Petroleum Inc.  
Name & Address Box 1447  
Great Bend, KS 67530

NE SW NE, SEC. 4, T 21 S, R 13 W/E  
3630 feet from S section line  
1650 feet from E section line

Lease Name Schaffer Unit Well # 3-3

County Stafford 116.42

Well Total Depth 3582 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 121

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Engineering License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 5:30 p.m. Day: 28 Month: 9 Year: 1987

Plugging proposal received from Deacon Pulley

(company name) Rockhold Engineering (phone) 316-792-2506

were: 5 1/2" at 3580' Perfs at 3409-13'

1st plug sand back to 3350' and dump 5 sx cement on top of sand through bailer,

2nd plug pump in 8 5/8" surface casing with 5 sx gel and 150 sx cement.

Plugging Proposal Received by Duane Rankin  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 5:45 p.m. Day: 28 Month: 9 Year: 1987

ACTUAL PLUGGING REPORT 1st plug sanded back to 3350' and dumped 5 sx cement with bailer,

2nd plug pumped in 8 5/8" surface casing with 5 sx gel and 150 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

Pumping pressure 100-200 psi and shut in 50 psi.

OCT 8 1987

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 424' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

**INVOLVED**  
do not observe this plugging.

DATE 10-9-87  
INV. NO. 18421

Signed Duane Rankin  
(TECHNICIAN)