

9-28-87 15.185.01677-0000

To: 1 120026
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- NA
NW SW NE, SEC. 4, T 21 S, R 13 W/X
3630 feet from S section line
2310 feet from E section line
Lease Name Schaffer Unit Well # 3-2
County Stafford 116.03
Well Total Depth 3570 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 131

TECHNICIAN'S PLUGGING REPORT
Operator License # 5238
Operator: Petroleum Inc.
Name & Address Box 1447
Great Bend, KS 67530

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 6 p.m. Day: 28 Month: 9 Year: 19 87

Plugging proposal received from Deacon Pulley

(company name) Rockhold Engineering (phone) 316-792-2506

were: 5 1/2" at 3568' Perfs at 3332-36'

1st plug sand back to 3280' and dump 5 sx cement on top of sand through bailer,

2nd plug pump in 8 5/8" with 5 sx gel and 150 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 7 p.m. Day: 28 Month: 9 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 3280' and dumped 5 sx cement on top of sand with dump bailer,

2nd plug pumped in 8 5/8" surface casing with 5 sx gel and 150 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 8 1987

Pumping pressure 250 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. No recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED
(If applicable) observe this plugging.

DATE 10-9-87
INV. NO. 18422

Signed Duane Rankin (TECHNICIAN)