

To: 1 120644
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

11-6
API NUMBER 15- 185-22,811.0000 74
SW SW NW, SEC. 31, T 21 S, R 12 W/E R

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039
Operator: L.D. Drilling, Inc.
Name & Address RR 1, Box 183 B
Great Bend, KS 67530

2970 feet from S section line
4950 feet from E section line
Lease Name Frank Well # 2
County Stafford 120.28
Well Total Depth 3701 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 331

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor L.D. Drilling, Inc. License Number 6039
Address RR 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: 11:45 p.m. Day: 5 Month: 11 Year: 19 91

Plugging proposal received from Greg Davidson
(company name) L.D. Drilling, Inc. (phone) 316-793-3051

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1873'
Anhydrite 675-700'
1st plug at Arbuckle with 40 sx cement, 2nd plug at 725' with 50 sx cement,
3rd plug at 370' with 50 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by _____ Case Morris
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 5 a.m. Day: 6 Month: 11 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 3640' with 40 sx cement,
2nd plug at 725' with 50 sx cement,
3rd plug at 375' with 50 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
11-7-91
NOV 7 1991
Wichita

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED
I (did / ~~did not~~) observe this plugging.

DATE 12-4-91
INV. NO. 33926

Signed [Signature]
(TECHNICIAN)

