

To: 1 120602
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

8-7 10
API NUMBER 15-185-22,791-0000
SE NW NW, SEC. 31, T 21 S, R 12 W/E
4290 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 6039
Operator: L.D. Drilling, Inc.
Name & Address: RR 1, Box 183 B
Great Bend, KS 67530

Lease Name Frank Well # 1
County Stafford 119.43
Well Total Depth 3675 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 320

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor L.D. Drilling, Inc. License Number 6039
Address RR 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: 3 p.m. Day: 7 Month: 8 Year: 19 91
Plugging proposal received from Greg Davidson

(company name) L.D. Drilling, Inc. (phone) 316-793-3051
were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1870'
Anhydrite 681-704'

- 1st plug at 700' with 50 sx cement,
- 2nd plug at 350' with 50 sx cement,
- 3rd plug at 40' with 10 sx cement,
- 4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Glenn R. Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____
Operations Completed: Hour: 5 p.m. Day: 7 Month: 8 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 700' with 50 sx cement,
2nd plug at 350' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
AUG 09 1991

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 8-27-91
INV. NO. 32844

observe this plugging.
Signed Duane Rankin (TECHNICIAN) R W Y

EFFECTIVE DATE: 8-7-91

FORM MUST BE TYPED
FORM C-1 4/90

State of Kansas
NOTICE OF INTENTION TO DRILL (88-2279) ALL BLANKS MUST BE FILLED
Must be approved by the K.C.C. five (5) days prior to commencing well

FORM MUST BE SIGNED

Expected Spud Date August 3 1991
month day year

SE. NW. NW. Sec 31. Twp 21. S, Rg 12. X East West

OPERATOR: License # 6039
Name: L. D. DRILLING, INC.
Address: R. R. 1 BOX 183 B
City/State/Zip: Great Bend, KS. 67530
Contact Person: L. D. Davis
Phone: (316) 793-3051

4290' feet from South line of Section
4290' feet from East line of Section
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 6039
Name: L. D. Drilling, Inc.

County: Stafford
Lease Name: FRANK Well #: 1
Field Name: GATES

Well Drilled For: Well Class: Type Equipment:
X Oil ... Inj X Infield X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OWD ... Disposal ... Wildcat ... Cable
... Seismic; ... # of Holes

Is this a Prorated Field? ... yes X no
Target formation(s): Arbuckle
Nearest lease or unit boundary: 990'
Ground Surface Elevation: EST. 1878 feet MSL
Domestic well within 330 feet: ... yes X no
Municipal well within one mile: ... yes X no
Depth to bottom of fresh water: 110'
Depth to bottom of usable water: 4250'
Surface Pipe by Alternate: X 1 ... 2
Length of Surface Pipe Planned to be set: 300'
Length of Conductor pipe required: none
Projected Total Depth: 3650'
Formation at Total Depth: Arbuckle
Water Source for Drilling Operations:

If OWD: old well information as follows:
Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth _____

... well ... farm pond ... other
OWR Permit #: applied for
Will Cores Be Taken? ... yes X no
If yes, proposed zone _____

Directional, Deviated or Horizontal wellbore? ... yes X no
If yes, total depth location: _____

AX-316-793-7237

AFFIDAVIT

AUG 09 1991

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

STATE CORPORATION COMMISSION
Wichita, Kansas

Pusher Greg Davidson
SPUD DATE 8-2-91 INIT. RL
LENGTH SURFACE PLANNED 300

RESERVE PIT STATUS- REMOVE FLUID _____ LINED _____
after salt sect. _____ bbls. _____ when done _____ bbls.

RATHOLED AHEAD? Y _____ N _____ SIZE HOLE _____
SURFACE PIPE X @ 322 CONDUCTOR _____
ANHYDRITE T- 68 B- 704 ELEVATION 1870

TD 3675 FORMATION Conglomerat
RAN PIPE @ _____ DV TOOL _____ ALT II DONE _____
_____ SX _____ Y _____ N _____

Arbuckle Plug @ _____ Ft. W/ 50 SX
Hug-/Council @ _____ Ft. W/ _____ SX
704 Anhydrite Base @ 700 Ft. W/ 50 SX
1/2 Base Anyh. @ _____ Ft. W/ _____ SX
1/2, 1/2 Plug @ _____ Ft. W/ _____ SX
Bottom Surface @ 350 Ft. W/ 50 SX
40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W LS SX MOUSE HOLE W/ _____ SX
WATER WELL _____ SX (Irr. Well _____ Pond _____)
Hauling _____
TECHNICIAN G.B. DATE 8-7-91

TYPE OF CEMENT 60/40 pos 690 jcl
STARTING TIME 3:00 (AM/PM) DATE 8-7-91
COMPLETION TIME 5:00 (AM/PM) DATE 8-7-91

CEMENT COMPANY Allied
D.A. Witnessed