

1 080400

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-21,791-0000
NW NW NE, SEC. 31, T 21 S, R 12 (W) X

4950 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7383

Lease Name Fischer Well # 2

Operator: Grady Bolding Corporation

County Stafford 120.25

Name & Address P. O. Box 244

Well Total Depth 3700 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 289

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address P. O. Box 698, Great Bend, KS 67530

Company to plug at: Hour: 1:20 pm Day: 18 Month: July Year: 19 85

Plugging proposal received from Deacon Pulley

(company name) Rockhole (phone) 316-792-2506

were: 5 1/2" at 3699' PBD 3475' Perfs at 3416-20'

1st plug sand back to 3350' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and 150 sx cement.

Plugging Proposal Received by J. N. Mead (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:10 pm Day: 18 Month: July Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 3350' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 150 sx cement.

STATE CORPORATION COMMISSION

7-22-85

JUL 22 1985

Maximum pressure 600 psi and shut in 300 psi

Remarks: Recovered 2500' 5 1/2" casing. Used 60/40 Pozmix 6% gel by BJ-Titan
(If additional description is necessary, use BACK of this form.)

INVOICED (do not observe this plugging.)

DATE 7-24-85

INV. NO. 9091

Signed J. N. Mead (TECHNICIAN)