

1080399

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 185-21,706.0000  
SW NW NE, SEC. 31, T 21 S, R 12 W/X  
4290 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7383

Lease Name Fischer Well # 1

Operator: Grady Bolding Corporation  
Name & Address: P. O. Box 244  
Great Bend, KS 67530

County Stafford 119.93  
Well Total Depth 3690 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 294

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Engineering, Inc. License Number 5111  
Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 3:30 pm Day: 18 Month: July Year: 19 85

Plugging proposal received from Deacon Pulley

(company name) Rockhold (phone) 316-792-2506

were: 5 1/2" at 3680' PBTB 3645' Perfs at 3411-15'

1st plug sand back to 3350' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, and 150 sx cement.

Plugging orders given by Paul A. Luthi

Plugging Proposal Received by J. A. Mead  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:30 pm Day: 18 Month: July Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 3350' and dump 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 22 1985 - 7-22-85

PL

Maximum pressure 700 psi and shut in 200 psi

Remarks: Recovered 2600' 5 1/2" casing. Used 60/40 Pozmix 6% gel by BJ-Titan  
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-24-85

INV. NO. 9092

Signed J. A. Mead  
(TECHNICIAN)