

3-23

133 R

To: 1-120389
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185.12909-0000
SW NWNW SEC. 31, T 21 S, R 12 WE

TECHNICIAN'S PLUGGING REPORT

0668 L 2
3-27-90

4290 feet from S section line
4950 feet from E section line

Operator License # 5245

Lease Name Fischer "A" Well # 3

Operator: OK Mar Oil Company
Name & Address Box 723
Hays, Kansas 67601
913-628-6101

County Stafford 120.22
Well Total Depth 3699' feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 329' @ 175SX

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 176 Chase Kansas

Company to plug at: Hour: 1:00 PM Day: 23 Month: 3 Year: 19 90

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) _____

work: 1st plug sand 5 1/2" casing back to 3275' & 55SX cement @ dump bailer
2nd plug 400# hulls, 10SX gel, 50SX cement, 10SX gel, 100# hulls & release
8 5/8" plug & 100SX cement

Plugging Proposal Received by Mike Wilson
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 PM Day: 23 Month: 3 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug Sanded 5 1/2" casing back to 3275' & 55SX cement @ bailer

2nd plug Pumped into 8 5/8" surface casing @ 400# hulls, 10SX gel, 50SX cement,
10SX gel, 100# hulls & 100SX cement

welded plate & 2" collar on top of 8 5/8" surface casing

Pumping Pressure 0-750 # Shut in Pressure 450 #

5 1/2" casing set @ 3765.58 cemented @ 175SX Cem. PBTD 3691 Perf @ 3325-3658' (9 sets)

Remarks: Cemented by Recovered 2600' of 5 1/2" casing

INVOICED

(Additional description is necessary, use BACK of this form.)

I did / did not observe this plugging.

DATE 4-6-90

Signed Dwan Rankin
(TECHNICIAN)

INV. NO. 27804