

To: 1 020371
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-19
API NUMBER 15-185-22,766.0000
160' W of
NW NE NE, SEC. 30, T 21 S, R 12 W/R
4950 feet from S section line
1150 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 6039
Operator: L.D. Drilling, Inc.
Name & Address: RR 1, Box 183 B
Great Bend, KS 67530

Lease Name Wayne Fischer Well # 1
County Stafford 118.00
Well Total Depth 3631 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 333

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Company License Number 5929
Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: 10:15 p.m. Day: 19 Month: 4 Year: 19 91
Plugging proposal received from John Armbruster
(company name) Duke Drilling Company (phone) 316-267-1331

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 682-704'
1st plug at 700' with 50 sx cement, 2nd plug at 360' with 50 sx cement,
3rd plug at 40' with 10 sx cement, 4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X
Operations Completed: Hour: 11:15 p.m. Day: 19 Month: 4 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 700' with 50 sx cement,
2nd plug at 350' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED (if desired) observe this plugging.

DATE 5-9-91
INV. NO. 31786

Signed Glenn Barlow
(TECHNICIAN)

EFFECTIVE DATE: 4-16-91

FORM MUST BE TYPED
FORM C-1 4/90

State of Kansas 185-22,766

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

NOTICE OF INTENTION TO DRILL

Must be approved by the K.S.C. five (5) days prior to commencing well

Expected Spud Date April 20 1991
month day year

160' W East
NW NE NE Sec 30 Twp 21 S Rg 12 West

OPERATOR: License # 6039
Name: L. D. DRILLING, INC.
Address: R. R. 1 BOX 183 B
City/State/Zip: GREAT BEND, KS, 67530
Contact Person: L. D. DAVIS
Phone: (316) 793-3051

4950 feet from South line of Section
1150 feet from East line of Section
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 5929
Name: DUKE DRILLING COMPANY

County: STAFFORD
Lease Name: WAYNE FISCHER Well # 1
Field Name: MUELLER

Well Drilled For: Well Class: Type Equipment:
Oil Inj Infield Mud Rotary
Gas Storage Pool Ext. Air Rotary
CWD Disposal Wildcat Cable
Seismic; # of Holes

Is this a Prorated Field? yes X no
Target Formation(s): KC/Arbuckle
Nearest lease or unit boundary: 330'
Ground Surface Elevation: 1863' feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water: 110'
Depth to bottom of usable water: 240'
Surface Pipe by Alternate: X 1 2
Length of Surface Pipe Planned to be set: 300'
Length of Conductor pipe required: none
Projected Total Depth: 3650'
Formation at Total Depth: Arbuckle

If CWD: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Water Source for Drilling Operations:
X well farm pond other
DWR Permit #: applied for
Will Cores be Taken? yes X no
If yes, proposed zone:

Directional, Deviated or Horizontal wellbore? yes X no
If yes, total depth location:

Exp. 10/11/91

AFFIDAVIT

260' Alt. I Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Pusher: John Ambrose

SPUD DATE 4-17-91 INIT. G.B.
LENGTH SURFACE PLANNED 300 + 8 1/8

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE @ CONDUCTOR
ANHYDRITE T- 68 B- 702 ELEVATION-

TD 363/ FORMATION
RAN PIPE @ DV TOOL ALT II DONE
SX Y N

Arbuckle Plug @ Ft. W/ 50 SX
Hug./Council @ Ft. W/ SX
Anhydrite Base @ 700 Ft. W/ 50 SX

1/2 Base Anyh. @ Ft. W/ SX
1/2, 1/2 Plug @ 350 Ft. W/ SX

2 Bottom Surface @ 360 Ft. W/ 50 SX
3 40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX

WATER WELL SX (Irr. Well Pond
TECHNICIAN DATE 4.23.91 Hauling

TYPE OF CEMENT 60/40 Pcs 698

STARTING TIME 10:15 (AM/PM) DATE 4-19-91

COMPLETION TIME 11:15 (AM/PM) DATE 4-19-91

CEMENT COMPANY Alicia