

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Ellis SEC. 5 TWP. 14 RGE. 19 X E/W  
Location as in quarters or footage from lines:  
NW SE SE


Lease Owner Kansas Petroleum, Inc.  
 Lease Name Orth Well No. 2 (SWD)  
 Office Address Suite 100, 200 E. First, Wichita, KS 6720  
 Character of Well (Completed as Oil, Gas or Dry Hole): SWD  
 Date Well Completed 1-20-67  
 Application for plugging filed 2-9-83  
 Plugging commenced 2-16-83  
 Plugging completed 2-17-83  
 Reason for abandonment of well or producing formation  
Deterioration of tubing and casing.

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion J. Schmidt

Producing formation N/A Depth to top  bottom T.D. 4070

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
		0	231	8 5/8	224.92	None
				with landing joint		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from  feet to  feet for each plug set.

No casinghead on 8 5/8" surface pipe; surface casing welded to 5 1/2" casing. Mixed and pumped 420 sax 50/50 Pozmix with 6% gel, 4 sax hulls; shut well in overnight. Pumped cement in well with 200# pressure. Cut surface pipe and 5 1/2" casing off. Found top of cement at 315' in 5 1/2" casing. Cement in 8 5/8" surface pipe was at 17 1/2'. Finished filling casing with Redi-mix cement, 2 yards. Put 1' cement in bottom of cellar.

(SEE ATTACHED PLUGGING REPORT OF STATE PLUGGER.)

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Halliburton Cementing

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

James Tasheff, officer of (Employer/Operator) xxx (xxxxxx) operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
Ste. 100, 200 E. First, Wichita,  
(Address) KS 67202  
Tele: 316-267-2266

SUBSCRIBED AND SWORN TO before me this 14th day of April, 19 83



Irene LaPrange  
Notary Public.

My Commission expires: