

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Ellis County, Sec. 5 Twp. 14S Rge. (E) 19 (W)

Location as "NE/CNW&SW&" or footage from lines NW SE SE

Lease Owner. Braden Drilling, Inc.

Lease Name Orth Well No. 2

Office Address 1620 Wichita Plaza, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed June 30, 19 66

Application for plugging filed June 30, 19 66

Application for plugging approved June 30, 19 66

Plugging commenced June 30, 19 66

Plugging completed June 30, 19 66

Reason for abandonment of well or producing formation D&A

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes Box

Name of Conservation Agent who supervised plugging of this well Leo Massey / 582, Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3920 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	231	8-5/8"	224.92'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Fluid found at 350', plug at 540 with 20 sacks cement. Fluid at 225 plugged with 20 sacks cement. Fluid to 40' plug and bridge, 1 sack. Job completed at 11:45 a.m.

RECEIVED
STATE CORPORATION COMMISSION

JUL 9 1966

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Company Tools

Address 1620 Wichita Plaza, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

James Tasheff

(employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

James Tasheff

1620 Wichita Plaza, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of July, 19 66

My commission expires

October 13, 1969

Marilyn Ann Smith

Notary Public.

DRILLER'S LOG

Braden Drilling, Inc.
ORTH #2
NW SE SE Sec. 5-14S-19W
Ellis County, Kansas

Commenced: June 23, 1966


Completed: June 30, 1966

Set 8-5/8" surface casing at 231' with
175 sacks cement (HA-5 Pozmix).

<u>Formation</u>	<u>From</u>	<u>To</u>
Rock and Sand	0	125
Blue Shale	125	1300
Shale and Shells	1300	1541
Anhydrite	1541	1586
Shale and Shells	1586	2450
Shale and Lime	2450	2610
Lime and Shale	2610	2805
Shale and Lime	2805	3367
Lime	3367	3920 T.D.


RECEIVED
STATE CORPORATION COMMISSION
JUL 8 1966
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that this is a true and correct log of the above
captioned well as shown by the daily drilling reports.


James Tacheff

Subscribed and sworn to before me this 7th day of July, 1966.

My commission expires: October 13, 1969


Marilyn Ann Smith
Notary Public